

---

# **ASHRAE RP1785 - PMS meeting**

## EXPERIMENTAL VALIDATION OF REFRIGERANT CHARGE MODELS IN COILS FOR RESIDENTIAL SPLIT SYSTEMS

Sponsor TC 8.11, Unitary and Room Air Conditioners and Heat Pumps  
Co-sponsor TC 8.4, Air-to-Refrigerate Heat Transfer Equipment and  
Co-sponsor TC 6.3, Central Forced Air Heating and Cooling Systems

06/23/2019

Abraham Lee<sup>1</sup>, Dr. Bach<sup>2</sup>, Dr. Bradshaw<sup>3</sup>  
Oklahoma State University

<sup>1</sup> Graduate Research Assistant,

<sup>2</sup> PI, and <sup>3</sup>Co-PI

---

# Acknowledgements

- **We would like to thank:**
  - Project management subcommittee (PMS)
  - Sponsoring and co-sponsoring committees
    - TC 8.11, TC 8.4, and TC 6.3
  - JCI, especially Dr. Kishan Padakannaya
  - Harrison-Orr, especially Damon McClure
  - Danfoss, especially Dan Schillinger
  - Temprite, especially Jim Nonnie
  - Henry Technologies, especially Aaron M. Arnold

---

# Agenda

- 1. Refrigerant Conditioning Loop**
- 2. Removable Heat eXchanger  
Charge Test Module(RHXCT)**
- 3. Volume-Measurement Device  
(VMD)**
- 4. Project Schedule**
- 5. Appendix**

---

# **Experimental Setup**

## **- Refrigerant Conditioning Loop**

# Refrigerant Conditioning Loop (Current status)

- The loop is ready to operate<sup>1)</sup>
- Data acquisition software has been developed<sup>1)</sup>



<sup>1)</sup> This loop built by Saad Saleem, to be used for RP1785 as well as OCAST project


---

**Removable  
Heat  
eXchanger  
Charge  
Test module  
  
(RHXCT)**


# Background

- RHXCT should  
: Detachable / Quick sampling/ Compact

- **Operating Mode (steady-state)**



- **Charge Sampling Mode**




- 1) Removable Heat exchanger Charge Test Module
- 2) Differential Mass Measurement Scale
- 3) Round tube plate fin heat exchanger

(M) (Motorized fast ball valves)

# Schematic Drawings of RHXCT

- Feature

- 1) Uniform refrigerant for individual circuit
- 2) Fast sampling







# Detailed Drawings of RHXCT

---

- 3D modeling




- Piping connections




# RHXCT (Current status)

- Module assembling is in progress

- RHXCT (in progress)




- Module part of RHXCT



# Individual Circuit Pressure Transducers

---

- To check pressure drop across the circuits for uniform refrigerant distribution.
- Calibrated in house w/ an accuracy of 0.07 PSI






# Pressure Sensors

- **Two pressure sensors at the coil inlet (Rated accuracy of 0.25 psi)**  
: Before and after expansion valves
- **Coil outlet pressure sensor (Rated accuracy of 0.65 PSI)**

- **Coil Inlet pressure sensor**



- **Coil outlet pressure sensor**




# RTDs and Thermocouple Quick Connectors

- **RTD - Installed to module's inlet and outlet pipes**  
(In-house calibration: Accuracy within 0.04 °F of reference thermometer reading)
- **TC - Installed to every return bends and hair pins**  
(In-house calibration: Accuracy within 0.4 °F of reference thermometer reading)

- **RTD**




- **TC**




# Pneumatic Fast Acting Shut-off Valves

- To sample refrigerant charge and oil retention installed at the inlet and outlet of RHXCT
- Measured closing time using a potentiometer on the valve's shaft is 0.06 sec. with good repeatability.

- Operation of the valve



- Closing time of the valve





	1 <sup>st</sup>	2 <sup>nd</sup>	3 <sup>rd</sup>
Each closing time(S)	0.059	0.062	0.048
Average closing time(s)	0.06		

---

# **Volume-Measurement Device (VMD)**

# Motivation of Volume-Measurement Device (VMD)


- Determination of volume is crucial for accurate charge prediction
- Every volume inside the RHXCT should be determined





# Volume-Measurement Device (VMD)

- A volume-measurement device (VMD) to measure internal volume of the RHXCT has been developed using "Gas Pycnometry"
  - VMD has been developed with  $\pm 0.1\%$  volume accuracy
- 
- Commercial gas pycnometer (Accuracy of volume measurement:  $0.02 \sim 0.2 \%^{1)}$ )




- 1** Inert gas flows into a sample chamber  
- valve **a** opens then closes
- 2** Equilibrium is reached
- 3** Gas flows into second chamber for volume measurement - valve **b** opens
- 4** Equilibrium is reached yet again
- 5** Volume is divided into sample weight determines density
- 6** Pressure vented off to atmosphere  
- valve **c** opens

# Principle

- Volume is determined by applying ideal gas law

$$\text{Test volume} = \left[ \left( \frac{P_1 T_3}{T_1} - P_3 \right) \times V_1 \right] / \left( P_3 - \frac{P_2 T_3}{T_2} \right)$$



$$\begin{aligned} P_1 V_1 &= m_1 R T_1 \\ P_2 V_2 &= m_2 R T_2 \\ P_3 V_3 &= m_3 R T_3 \\ P_3 V_3 &= (m_1 + m_2) R T_3 \end{aligned}$$

$$\begin{aligned} P_3 (V_1 + V_2) &= \frac{P_1 V_1 T_3}{T_1} + \frac{P_2 V_2 T_3}{T_2} \\ V_2 &= \frac{\left[ \left( \frac{P_1 T_3}{T_1} - P_3 \right) \times V_1 \right]}{P_3 - \frac{P_2 T_3}{T_2}} \end{aligned}$$

If  $T_1 = T_2 = T_3$ , then

$$V_2 = \frac{(P_1 - P_3) \times V_1}{P_3 - P_2}$$

# Target Accuracy of VMD

- Target accuracy: 4.9 ml
- % error (vol. error / V\_estimated) =  $4.9/1650 * 100 \% = 0.3 (\%)$

▪ IC1 coil  
Condenser test

▪ Target accuracy of  
mass measurement  
= 1 g

▪ Estimated  
approximate coil  
volume using  
internal diameter :  
1650 ml

▪ Estimation of mass  
of coil = 336.8 g<sup>1)</sup>

▪ Add 1g uncertainty :  
337.8 g of coil mass



▪ Revised volume of  
coil to have 337.8 g  
= 1654.9 ml

▪ Allowable Volume  
error = 4.9 ml

▪ % error (vol. error / Vol.\_estimated)  
=  $4.9\text{ml}/1650\text{ml} * 100 \% = 0.30 (\%)$

# Validation of VMD


- $\pm 0.1 \%$  error (within the target %error, 0.3%)<sup>1)</sup>
- $\pm 1.0$  ml error (within the target error, 4.9 ml)<sup>1)</sup>



- VMD total uncertainty =  $\pm 2.5$  ml
- Water total uncertainty =  $\pm 0.8$  ml

1) Against water filling method  
2) GE Druck  $\pm 0.0075$  psig, ThermoProbe Inc.(TL1-A):  $\pm 0.1$  °F

# Project Schedule



## Future Work

---

- **Complete volume measurement of RHXCT**
- **Commissioning overall setup**
- **Developing refrigerant & oil loop (independent task)**

---

# Appendix

## Evaporator\_Target\_accuracy of volume measurement – Using EES

---


- **Target accuracy of mass measurement = 1 g**
- For IC1 coil
- Estimated coil volume using internal diameter : 1650 ml
- Assume quality=0.5,  $t_{\text{eva}} = 50 \text{ F}$
- Estimated mass of coil = 133.4 g
- Add 1g uncertainty → 134.4 g of coil mass
- Revised volume of coil to have 134.4 g = 1662 ml
- **Allowable Volume difference = 12 ml**
- **% error (vol. diff. /  $V_{\text{estimated}}$ ) =  $12/1650 * 100 \% = 0.75 (\%)$**



# Initial Test Matrix


- Initial test matrix as per TRP is shown below

- Three factors**



- Test matrix<sup>1),2)</sup>**

(Black dots represent test runs that will be done)



*Table 8: Evaporator Mode Test Conditions (1785-TRP's Table 2)*


Evaporator Independent Variables		Indoor Coil (AC)	Outdoor Coil (HP)
Airflow	CFM	As required	As required
Reference liquid temperature	(°F)	100-110	90-100
Outlet superheat	(R)	5-20	5-20
Refrigerant Flow	lb/hr	150, 350, 500	100, 300, 400
Air Inlet Temperature(s)	(°F)	80	47

- The subcooling will be determined and fixed
- Keep the same inlet quality


# Refrigerant Flow in RHXCT

- Four EXVs control mass flow rate in each circuit
- Pressure regulator controls evaporation temperature

- Schematic of the refrigerant flow in “Evaporator Test”




# Refrigerant Loop Diagram



# Refrigerant Loop for no-oil Tests as Part of Task 3

- Oil loop to be added as parallel task for future tests with refrigerant-oil mixtures.



## Legend

Ref. conditioning loop<sup>1)</sup>

Hot water loop<sup>1)</sup>

# Refrigerant & Oil Conditioning Loop (Planed<sup>2</sup>)

## Legend


Refrigerant Loop

Oil Loop

Ref. conditioning loop<sup>1)</sup>

Hot water loop<sup>1)</sup>

Oil Separation Loop



# Test Conditions

*Table 7: Condenser Mode Test Conditions (1785-TRP's Table 1)*

Condenser Independent Variables		Indoor Coil (HP)	Outdoor Coil (AC)
Airflow	CFM	As required	As required
Inlet Superheat	(R)	30-60	30-60
Liquid temperature	(°F)	90-100	100-110
Refrigerant Flow	lb/hr	100, 300, 400	150, 350, 500
Air Inlet Temperature(s)	(°F)	70/60	95/75

*Table 8: Evaporator Mode Test Conditions (1785-TRP's Table 2)*

Evaporator Independent Variables		Indoor Coil (AC)	Outdoor Coil (HP)
Airflow	CFM	As required	As required
Reference liquid temperature	(°F)	100-110	90-100
Outlet superheat	(R)	5-20	5-20
Refrigerant Flow	lb/hr	150, 350, 500	100, 300, 400
Air Inlet Temperature(s)	(°F)	80	47

(Source: 1785-TRP)

- Note, Indoor coil tests require 1slab airflow rate and refrigerant flow rate (e.g. (150/2) lbm/hr, (500/2) lbm/hr)

# The Selected Coils

- **PMS<sup>3)</sup> has selected several sets of coils**

- **Naming<sup>4)</sup>**

**OC : Outdoor Coils**  
**IC : Indoor Coils**

- **The selected coils' internal volume<sup>1)</sup> ratio**

OC/IC ratio <sup>1)</sup>		Denominator	
		IC1 <sup>2)</sup>	IC2 <sup>2)4)</sup>
Numerator	OC1	160%	89%
	OC2	182%	101%
	OC3	N.A	212%

- **Test condition(Air flow rate)**  
: By experiment<sup>5)</sup>

1) OC/IC = the internal volume of outdoor coil / the internal volume of indoor coil

2) The indoor coils are two slabs

3) (Research) Project Management Subcommittee

4) Coil name changed; ID7→IC2, ID1 →IC1, OD1→OC1, OD2→OC2, OD3→OC3

5) Airflow rate will be determined by the experiments

: Outdoor coils@3ton capacity as per Proposal for Research on ASHRAE Project 1785-TRP

: Indoor coils@1.5ton capacity as per Proposal for Research on ASHRAE Project 1785-TRP


: RP1785 Objectives(Obtaining data for 3-ton indoor/outdoor coils)

# The Indoor Coil's Information


- Coil's information

Indoor	Name	Row	Tube length	Coil Height	Tube Type	Tube Thickness	Fin Type	FPI <sup>1)</sup>	Note
	IC1	3	17.5"	16"	Smooth	0.012	Sine	14	2 slab
	IC2	3	17.5"	28"	Smooth	0.012	Sine	14	2 slab

Unit=inch



IC1



IC2


1) Fins per inch; JCI plant standard




# The Outdoor Coil's Information

- Coil's information


Outdoor	Name	Row	Tube length	Coil Height	Tube Type	Tube Thickness	Fin Type	FPI <sup>1)</sup>
	OC1	2	48"	30"	Smooth	0.020	Sine	20
	OC2	2	48"	34"	Smooth	0.020	Sine	20
	OC3	2	72"	48"	Rifled	0.012	Louver	20



**OC1**



**OC2**



**OC3**

Unit=inch

1) Fins per inch; JCI plant standard

# Coil circuit

